
SIENA STONE 333®

RETAINING WALL GEOGRID SECTION

2410mm (7.90ft) Site: 3H:1V Slope - Clays Infill: Granular



	Design S	pecific	Geometric	Information
--	----------	---------	-----------	-------------

Retaining Wall System	SienaStone333 w/ Geogrid	Geogrid Type and Manufacturer	See Notes			
Maximum Height mm (in)	2410 (94)	Minimum Geogrid LTDS kN/m (lb/ft)	See Notes			
Maximum Slope Above Wall	1V:3H	Maximum Slope Below Wall	None			
Max. Surcharge Above Wall kPa (lb/sq.ft)	None	Depth of Embedment mm (in)	239 (9)			
Batter of Wall	7.12 •	Compacted Base Dimension mm (in)	702 x 186 (28 x 7)			

Design Specific Soil Information

Soil Region					
Infill	Retained	Foundation	Base	Drainage	
GW Well graded, free draining Granular	CL Inorganic Clays Low Plasticity	CL Inorganic Clays Low Plasticity	GW Well graded, free draining Granular	see infill	
35 [°]	28	28	39 [°]	NR	
22 (140)	20 (127)	20 (127)	22 (140)	NR	
NR	NR	NR	NR	NR	
Placed in 150mm (6") lifts and compacted to 95% SPD.	Undisturbed dense soil or well compacted Eng. fill.	Allowable bearing cap.must exceed 100kPa (2100 psf)	Crushed Gravel (free draining) compacted to 98% SPD.	Gravel infill must be well graded, angular, free drain w/max. 8% fines	
	GW Well graded, free draining Granular 35 [°] 22 (140) NR Placed in 150mm (6°) lifts and compacted to 95%	GW CL Well graded, free draining Granular Inorganic Clays 35° 28° 22 (140) 20 (127) NR NR Placed in 150mm (6°) filts and compacted to 55% Undisturbed dense soil or compacted to 55%	Infili Retained Foundation GW CL <td>Infill Retained Foundation Base GW CL CL GW Well graded, free draining Granular Inorganic Clays Inorganic Clays Well graded, free draining Granular 35° 28° 28° 39° 22 (140) 20 (127) 20 (127) 22 (140) NR NR NR NR Placed in 150mm (6°) filts and compacted to 55% Undisturbed well compacted Allowable bearing cap.must exceed firee draining) Crushed Gravel firee draining</td>	Infill Retained Foundation Base GW CL CL GW Well graded, free draining Granular Inorganic Clays Inorganic Clays Well graded, free draining Granular 35° 28° 28° 39° 22 (140) 20 (127) 20 (127) 22 (140) NR NR NR NR Placed in 150mm (6°) filts and compacted to 55% Undisturbed well compacted Allowable bearing cap.must exceed firee draining) Crushed Gravel firee draining	

Notes:

1. This design meets or exceeds the minimum factors of safety required by Risi Stone Systems based on the design parameters listed above. The analysis was performed as outlined in the National Concrete Masonry Association Design Manual for Segmental Retaining Walls, Third Edition. This is a typical, non site-specific Design.

2. No analysis of global stability, total or differential settlement, or seismic effects has been performed.

3. This design is only provided to illustrate the general arrangement of the SRW structure for preliminary costing and feasibility purposes only. This drawing is not for construction. A qualified Engineer must be retained to provide the Final Design prior to construction.

4. Structures such as handrails, guardrails, fences, terraces, and site conditions such as water applications, drainage and soil conditions, additional live and dead loads, etc., have significant effects on the wall design and have not been taken into account in this typical section. When accounted for in the Final Design, other conditions and elements may result in additional design measures (geogrid, drainage, etc) and cost.

5. For geogrid reinforced structures, a minimum Long Term Allowable Design Strength of 14 kN/m was assumed.

Contact your manufacturer or Risi Stone Systems for a list of approved geogrid reinforcements.



Engineering design by RisiStone Inc.

JNILOCK[®] PAVERS & WALLS

UNILOCK.COM | 1-800-UNILOCK