
SIENA STONE®

RETAINING WALL GEOGRID SECTION

1300mm (4.26ft) Site: 3H:1V Slope - Clays Infill: Granular



Desian S	Specific	Geometric	Information

Retaining Wall System	SienaStone w/ Geogrid	Geogrid Type and Manufacturer	See Notes
Maximum Height mm (in)	1300 (51)	Minimum Geogrid LTDS kN/m (lb/ft)	See Notes
Maximum Slope Above Wall	1V:3H	Maximum Slope Below Wall	None
Max. Surcharge Above Wall kPa (lb/sq.ft)	None	Depth of Embedment mm (in)	186 (7)
Batter of Wall	7.12 •	Compacted Base Dimension mm (in)	879 x 186 (35 x 7)

Design Specific Soil Information

Infill GW I graded, free ning Granular 35°	Retained CL Inorganic Clays Low Plasticity 28 °	Foundation CL Inorganic Clays Low Plasticity 28 °	Base GW Well graded, free draining Granular 39°	Drainage see infill NR
l graded, free ning Granular	Inorganic Clays Low Plasticity	Inorganic Clays Low Plasticity	Well graded, free draining Granular	
	28 [°]		39 [°]	NR
22 (140)	20 (127)	20 (127)	22 (140)	NR
NR	NR	NR	NR	NR
fts and		cap.must exceed 50kPa (1050 psf).	(free draining) compacted to 98%	Gravel infill must be well graded, angular, free drain w/max. 8% fines
A	d in 150mm ts and	d in 150mm Undisturbed dense soil or acted to 95% well compacted	d in 150mm Is and dense soil or cap.must exceed acted to 95% well compacted 50kPa (1050 psf).	In 150mm Undisturbed Allowable bearing Crushed Gravel is and dense soil or cap.must exceed (free draining) acted to 95% well compacted 50kPa (1050 psf). compacted to 98 %.

Notes:

1. This design meets or exceeds the minimum factors of safety required by Risi Stone Systems based on the design parameters listed above. The analysis was performed as outlined in the National Concrete Masonry Association Design Manual for Segmental Retaining Walls, Third Edition. This is a typical, non site-specific Design.

2. No analysis of global stability, total or differential settlement, or seismic effects has been performed.

3. This design is only provided to illustrate the general arrangement of the SRW structure for preliminary costing and feasibility purposes only. This drawing is not for construction. A qualified Engineer must be retained to provide the Final Design prior to construction.

4. Structures such as handrails, guardrails, fences, terraces, and site conditions such as water applications, drainage and soil conditions, additional live and dead loads, etc., have significant effects on the wall design and have not been taken into account in this typical section. When accounted for in the Final Design, other conditions and elements may result in additional design measures (geogrid, drainage, etc) and cost.

5. For geogrid reinforced structures, a minimum Long Term Allowable Design Strength of 14 kN/m was assumed.

Contact your manufacturer or Risi Stone Systems for a list of approved geogrid reinforcements.



Engineering design by RisiStone Inc.



UNILOCK.COM | 1-800-UNILOCK