

# SUNSET FIRE PIT

THICKNESS 300MM  
REGION OHIO



**UNILOCK** Exclusive Technologies

CLASSIC COAT



APPLICATIONS

Note: Not all sizes are suitable for every application. Contact Unilock Representative for assistance.



Fire Features

COLORS

RIVER  
FINISH: ANTIQUED /  
PROCESSED



**SQUARE W/INSERT**  
1,100mm x 1,100mm x 300mm  
43 3/8" x 43 3/8" x 11 7/8"



**ROUND W/INSERT**  
1,300mm x 1,300mm x 300mm  
51 1/4" x 51 1/4" x 11 7/8"

LIMESTONE  
FINISH: ANTIQUED /  
PROCESSED



**ROUND W/INSERT**  
1,300mm x 1,300mm x 300mm  
51 1/4" x 51 1/4" x 11 7/8"



**SQUARE W/INSERT**  
1,100mm x 1,100mm x 300mm  
43 3/8" x 43 3/8" x 11 7/8"

SIERRA  
FINISH: ANTIQUED /  
PROCESSED



**ROUND W/INSERT**  
1,300mm x 1,300mm x 300mm  
51 1/4" x 51 1/4" x 11 7/8"



**SQUARE W/INSERT**  
1,100mm x 1,100mm x 300mm  
43 3/8" x 43 3/8" x 11 7/8"

SANDSTONE  
FINISH: ANTIQUED /  
PROCESSED



**ROUND W/INSERT**  
1,300mm x 1,300mm x 300mm  
51 1/4" x 51 1/4" x 11 7/8"



**SQUARE W/INSERT**  
1,100mm x 1,100mm x 300mm  
43 3/8" x 43 3/8" x 11 7/8"

TYPICAL CROSS SECTION

Note: Base, screed bed, infill aggregates and or reinforcements may vary based on project requirements or as specified by engineer.

---



PACKAGING

	SQUARE W / INSERT	ROUND W / INSERT
UNIT THICKNESS (MM)	300	300
LAYERS PER BUNDLE	3	3
UNITS PER BUNDLE	36	54
UNITS PER LAYER	12	18

## INSTALLATION NOTES

---

### Sunset Fire Pit

Standard Base – Min. 6" – 8" of ¾" Crusher Run gravel (any road base standard in accordance with ASTM-D2940) compacted to 98% Standard Proctor Density (SPD).

Levelling – Leveling fire pit kits directly on top of gravel is tedious and generally does not yield the best results. U-Grip™ Base units or universal base pads are recommended under all Unilock walls for improved accuracy and makes for a speedier installation. Additional benefits include long term structural integrity and an overall better appearance. Poured concrete leveling pads, reinforced with rebar, are also a great way to accomplish leveling, especially for larger installations. You must ensure that the concrete is poured and finished perfectly in order to achieve a good visual appearance.

Connection – Fire pit wall units must be glued using an appropriate high heat concrete adhesive for connection between units. Always read adhesive manufacturers' directions prior to gluing.

Handling – Handle wall units with care when installing. Bumping units into one another may chip the face.

Coping – No coping is required for the Sunset fire pit.

---

Contact Unilock Representative for actual color samples and availability. Unilock reserves the right to change product information without notice.

PDF Generated April 24, 2024, 4:04 pm

**UNILOCK**